

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 9/17 19 94

McDani
 ACTING Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-266

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>05</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on August 14, 1993, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D5: P.L.S., Alfred Millard, DS, 1852. Set quarter section post. Maple 12, S.52 E., 38 links. Hemlock 10, N.70 W., 53 links. No subsequent resoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D5: Ran corrected compass line on G.L.O. Bearing east from section corner 7, 8, 17 & 18, to 40.0 chains. A search was made at original BT locations for remaining evidence of Maple and Hemlock. At N.70 W., 50 links found remains of Hemlock roots in stump hole. At S.52 E., 38 links found 24" Maple w/blaze scars, an original BT alive and standing. From Maple estab. corner position in small swamp hole and found 14" long axe pointed post point. Installed monument at post point location and estab. new reference trees. Section corner to west 40.0 chains supports this corner position and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D5: Set 2 1/4" x 30 Alum. Non. w/3 1/4" Alum. cap stamped to I.D. corner. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Y. Birch 12", N.30 W., 45.63 feet, '1/4S-BT'. Cedar 14", N.74 E., 33.83 feet, '1/4S-BT'. Hemlock 14", S.42 E., 33.10 feet, '1/4S-BT'. Black Ash 6", S.64 W., 61.68 feet, Not Scrd. Survey Marker Sign, South 1.0 feet.

Signed by Robert L. Jamros Date 10 July, 1994
 Surveyor's Michigan License No. 25849