

Donald W. Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-305

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>07</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			<u>COMMISSION</u>
5. Private Claims _____			

FILED
 APR 9 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
 REG.

Register of Deeds Stamp & File Number

COMMISSION

I, Robert L. Jamros, in a field survey on November 30, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

D7: PLS-Alfred Millard, DS, 1852, Set Qr. Section Post- Hemlock 18", N.10 E., 20 links, Hemlock 18", S.20 W., 13 links. CCI Forestry Division, Land and Timber Examination Report, R.Radcliffe, RLS, 1949, indicates stake at corner position. No references given. Frank J. Bray, RLS, 1973, This corner was set from old signature trees and blaze lines. New witnesses: 5' Hemlock, N.52 W., 22.9 ft., 5' Hemlock, S.32 W., 13.2 ft., All bearings are magnetic., Filing No. 34, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D7: Found 1 1/4" G.I.P. with 4" Alum. cap marked to identify corner position, and a squared 4" Cedar post. Found blaze lines north and south and blaze line west. Section corner to the east common to Sections 16-17-20-21 was recovered in 1993 using this corner at 40.11 chains from this corner. A search was made for original BT's at GLO BT locations and results inconclusive. 1973 report, Filing no. 34, A.C.Records states corner was established from two old signature trees and blaze line north and south and blaze line west. Found BT's of 1973 report in excellent condition. Established additional reference trees. Corner lies in flat, open area of mixed timber. Corner position is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D7: Found 1" pipe w/ 4" Alum. Cap, a fallen tree has broken edge of cap off. Stamped P.A. 345 on cap and renewed existing reference trees w/ BT signs and paint. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in all the following reference trees. Ex. Hemlock 8", N.51 W., 22.93 feet, 'Dbl Blz', Ex. Hemlock 8", S.31 W., 13.51 feet, 'Dbl Blz', Twin Hemlock 6", N.38 E., 57.65 feet, '1/4s BT', Maple 11", S.31 E., 63.04 feet, '1/4s BT', Steel witness post with Survey marker sign, S.29 W., 1.6 feet. All bearings are magnetic.

Signed by Robert L. Jamros
 Surveyor's Michigan License No. 25849

Date 12 April, 1995