

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-308

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>09</u>	SURVEY & REMONUMENTATION MAY 10 1995 COMMISSION
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	

FILED
E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
EG

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. James, in a field survey on December 02, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9				●									
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D9: PLS-Alfred Millard, DS, 1852, Set Qr. Section Post- Maple 8", N.58 E., 19 links, Maple 12", S.60 W., 8 links. CCI Forestry Division, Land and Timber Examination Report, E.C. Anderson, 1941, shows cedar post and GLO Maple BT at corner position. Frank J. Bray, RLS, 1973, This corner was replaced from old original BT, Maple 12, S.60 W., 8 links. This tree has upper face with scribe marks and is still growing. Found old down wood post. Witnesses: 12' Hemlock, N.37 E., 27.1 ft., 12' Hemlock, S.35E., 19.7 ft., All bearings magnetic. Filing No. 34, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D9: Found 1 1/4" 6.I.P. with 4" Alum. cap marked to identify corner position, and squared 4" post scribed 1/4S, 29, 20, on faces. Corner position was recovered from original BT, Maple 12, S.60 W., 8 links, as stated in 1973 report. Filing no. 34, A.C. Records. Found GLO BT, 20" Maple stub at S.60 W., 8 links from monument, scribing and notch still visible. Existing reference BT's in excellent condition. Established additional reference BT's. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D9: Stamped P.A. 345 in existing 4" Alum. capped Michigan D.N.R. Monument. Renewed existing reference trees w/ BT signs and paint. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails w/ brass I.D. washers in all of the following reference trees. Ex. Hemlock 16", N.38 1/2 E., 27.52 feet, "1/4s BT", Ex. Hemlock 16", S.34 E., 20.05 feet, "1/4s BT", Hemlock 10", S.32 W., 32.58 feet, "1/4s BT", Hemlock 22", N.61 W., 47.34 feet, "1/4s BT", Steel witness post with Survey marker sign, N.14 E., 2.0 feet. All bearings are magnetic.

Signed by Robert L. James Date 12 April, 1995
Surveyor's Michigan License No. 25849