

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 9/12 1994

McLachlan
ACTING Chairman
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-265

FILED
TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>E4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. James, in a field survey on June 29, 1993, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E4: P.L.S., Alfred Millard, DS, 1852. Set quarter section post. Hemlock 15, N.62 E., 17 links. Maple 15, S.45 W., 13 links. George L. Depew, County Surveyor December 1917, set iron corner from Gov't field notes. Gerald W. Carlson, R.L.S., April 1979, found 1 1/2" iron pipe w/brass cap, 2' high, centerline of road to North, approx. 20 feet South of East-West road. Established references, 12' Maple, S.20 W., 43.50 feet, Maple Cluster, S.71 W., 40.04 feet, Maple Cluster, S.10 E., 54.74 feet, Power Pole, S.83 E., 24.72 feet. Recorded in filing NO. 279, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E4: Found 2" G.I.P. w/brass cap, identified by references on recorded report, monument dated March 7, 1917, 2.0 feet above ground and bent over beyond repair. Corner position is 22 feet South of E-W road and on centerline of road to North. Corner set by George L. Depew, CS, in 1917, from Gov't field notes. Corner recovered by Gerald W. Carlson, R.L.S., in 1979. Damaged corner monument was replaced. Corner reference BT's were found as set and relate to corner position as recorded. Corner position sets well with record information and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E4: Set 2 1/4" x 30" Alum. Mon. w/3 1/4" Alum. cap stamped to I.D. corner. Renewed existing reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers. Ex. Maple 18", S.16 W., 43.84 feet. Ex. Maple Cluster 4-8", S.11 E., 55.14 feet, "1/4S-BT". Ex. Maple Cluster 3-12", 1-18", S.66 W., 39.85 feet. Ex. Power Pole w/trans., S.83 E., 24.71 feet, "BT". Survey Marker Sign, South 0.60 feet.

Signed by Robert L. James Date 10 July, 1994

Surveyor's Michigan License No. 25849