

Approved by Alger County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of  
 P.A. of 1990 On 9/7 1994

McEwen  
 ACTING Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

4-264

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>E5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED  
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN  
 REGISTER OF DEEDS  
 ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 14, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E5: P.L.S., Alfred Millard, DS, 1852. Set post corner of Sections 8, 9, 16 & 17. Cedar 10, N.42 W., 24 links. Cedar 15, S.45 E., 5 links. C.C.I. Co. Forestry Records, Land & Timber Examination Reports, 1940 thru present. Reports indicate 4" stake and 12" down Cedar BT, no references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E5: Ran corrected compass line on G.L.O. Bearing east from section corner 7, 8, 17 & 18 and 1/4 section 8 - 17 to 80.0 chains. Found downed 4" stake and remains of downed Cedar BT., as indicated on C.C.I. Co. Forestry Records. Installed monument in stake point hole, and estab. new reference trees. Section corner at 80.0 chains and 1/4 Section corner at 40.0 chains to west support this corner position and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E5: Set 2 1/4" x 30 Alum. Mon. w/3 1/4" Alum. cap stamped to I.D. corner. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Maple 9", N.17 E., 19.75 feet, S9-BT". Maple 11", S.62 E., 29.62 feet, S16-BT". Maple 10", S.53W., 40.86 feet, S17-BT". Maple 9", N.64 W., 15.29 feet, S8-BT". Survey Marker Sign, South 1.0 feet.

Signed by Robert L. Jamros Date 10 July, 1994

Surveyor's Michigan License No. 25849