

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 9/17 1994

Mc Davis
ACTING Chairman
For corners in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-263

FILED
TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

Alger (County) Located In: Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>E7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. James, in a field survey on September 22, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E7: P.L.S., Alfred Millard, DS, 1852. Set post corner of Sections 16, 17, 20 & 21. Sugar 12, N.45 W., 58 links. Sugar 12, S.30 E., 30 links. Michigan Department of Conservation, Frank J. Bray, 1973. Corner was set from two old signature trees. Blaze line north and south and blaze line west. Set 1" pipe w/ 4" Alum. cap. Est. references, 5" Hemlock, N.52 W., 22.9 ft., 5" Hemlock, S.32 W., 13.2 ft. Recording no. 34, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E7: Found two peeled posts at corner positions lying 50 feet SEly of centerline of woods road. Search was made at original BT locations, evidence found was inconclusive. Found alum. location tag (C.C.I.) on 24" Maple on westerly side of woods road, marked "35 pcs east to corner. Ran corrected compass line on G.L.O. Bearing east to G.L.O. line tree call of 9.80 chains, Cedar 6", running parallel to old blaze line. Marked a decayed 14" Cedar stump on our line at 9.74 chains and accepted as line tree remains. Ran corrected compass line on G.L.O. Bearing North to G.L.O. line tree call of 9.80 chains, Cedar 12", following old blaze line. Marked a decayed 18" Cedar stump 2 feet west of our line at 9.82 chains and accepted as line tree remains. Ran corrected compass line on G.L.O. Bearing west and found a 1" G.I.P. w/4" Alum. cap (M.D. of C.) monument and two reference trees at 40.11 chains. Installed monument at location of two posts and estab. new reference trees. Lines ran to East, North and West to exist. monument support this corner position and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E7: Set 2 1/4" x 30" Alum. Mon. w/3 1/4" Alum cap stamped to I.D. corner. Est. reference trees w/BT signs, blazed, scribed and painted. Set Pk nails for measuring w/brass I.D. washers in the following reference trees. Maple 5', S.50 W., 9.21 feet, "S20-BT". Hophornbeam 8", S.72 E., 50.58 feet, "S21-BT". Maple 14", N.21 E., 66.69 feet, "S16-BT". Twin Maple 6" - 4", N.47 W., 35.05 feet, "S17-BT". Survey Marker Sign, North, 1.2 feet.

Signed by Robert L. James
Surveyor's Michigan License No. 25049

Date 10 July, 1994