

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 9/17 1994

McDermis
ACTING Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-262

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>E9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Jamros, in a field survey on September 15, 1993, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E9: P.L.S., Alfred Millard, DS, 1852. Set post cor. of Sections 20, 21, 28 & 29. Beech 12, N.45 E., 41 links. Hemlock 30, S.48 W., 18 links. C.C.I. Forestry Division, Ray J. Brotherton, R.L.S., 1955, Set 3" iron spring leaf from Gov't line tree stub Yellow Birch, notches plain, established references as follows: 16" Hemlock, S.69 E., 47 1/2 links, 10" Hemlock, N.29 1/2 W., 69 1/2 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E9: Found 3" iron spring leaf, identified by references on record report, 17 feet SEly from centerline to main woods road. Found two sq'd 3" posts 2.3 feet NEly of corner position. Installed monument in place of iron spring leaf and estab. new reference trees and renewed two existing BT's. Subsequent restoration by R.J. Brotherton, R.L.S., from stub of Gov't Y. Birch line tree sets this corner position and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E9: Set 2 1/4" x 3/8" ALUM. MON. W/3
1/4" Alum. cap stamped to I.D. corner.
Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Hemlock 14", N.27 W., 47.14 feet, "S20". Ex. Hemlock 23", S.68 E., 31.69 feet, "S28". Maple 6", N.14 E., 76.61 feet, "S21-BT". Maple 8", S.18 W., 11.90 feet, "S29-BT". Survey Marker Sign, S.38 E., 0.8 feet.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25649

Date 10 July, 1994