

Donald W. Carlson  
 Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

4-310

For corners in

Alger  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 22W  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

E10 \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

MAY 10 1995

COMMISSION

FILED  
 E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN  
 EG

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. James, in a field survey on October 26, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E10: PLS-Alfred Millard, DS, 1852, Set Gr. Section Post- Sugar 10", N.68 E., 8 links, Sugar 12", S.66 W., 34 links. CCI Forestry Division, Land corner record page 979, Robin D. Steinhoff, 1967, Brass Cap Iron at corner, also original (NE) BT alive and standing. New references: Hemlock 8", N.55 W., 17 links, Maple 3", S.33 W., 11 1/2 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E10: Found 2" cast steel monument with 3 1/4" brass cap marked to identify corner position, Nov. 8, 1910. Found original GLO BT at N.68 E., 8 links, Maple 8" now a 28" Maple and still alive. Found monument, original BT and new BT's of report of Robin D. Steinhoff, 1967, in excellent condition. Found old blaze lines north and south. Established additional reference trees. Corner lies in open and high area of mixed timber. Existing Corner Monument is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E10: Stamped P.A. 345 in brass cap of cast steel monument. Renewed existing reference trees w/BT signs and paint. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Maple 8", S.36 W., 7.62 feet, "Dbl Blz", Ex. Hemlock 10", N.50 W., 11.37 feet, "Dbl Blz", Maple 14", N.44 E., 37.10 feet, "1/4s BT", Maple 15", S.33 E., 58.92 feet, "1/4s BT", Steel witness post with Survey marker sign, S.68 E., 2.0 feet. All bearings are magnetic.

Signed by Robert L. James  
 Surveyor's Michigan License No. 25849

Date 12 April, 1995