

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 4-8-1995

Donald W. Kinnunen
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-312

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	E11
	T _____ R _____	SURVEY &
	T _____ R _____	REMONUMENTATION
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	<u>MAY 10 1995</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	COMMISSION

FILED
9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
 FC

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on November 29, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E11: PLS-Alfred Millard, DS, 1852, Set post corner of sections 28,29,32 and 33, - B.Ash 12', S.25 E., 16 links, B.Ash 10", N.42 W., 20 links. CCI Forestry Division, Land and Timber Examination Report, R.J. Brotherton, RLS, 1940, indicates 3" post and down original B.Ash BT at corner location. CCI Land Corner Record Page 108, J.R. Radcliffe, RLS, 1963, Wood post here set by R.J. Brotherton, many old registers here and old Cedar post with notches according to GLO survey instructions. New references: Hemlock 6", S.75 W., 25.5 links, Y.Birch 11", N.13 E., 5.0 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E11: Found cruisers post and alongside under water and swamp bottom found post point believed to be original. Found new BT's as established in report of J.R.Radcliffe, 1963. Hemlock in good condition and Y.Birch dead and just a stub. Found old blaze lines east and west and blaze line north. Replaced existing post point with new monument and established additional reference trees. Corner lies in wet swamp area of mixed lowland timber. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E11: Set 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to identify corner position. Renewed existing reference trees w/BT signs and paint. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Cedar 11", S.34 E., 45.90 feet, "S33 BT", Cedar 6", N.76 E., 26.81 feet, "S28 BT", Ex. Hemlock 8", S.72 W., 16.71 feet, "Crown Blaze Notch", Hemlock 5", N.40 W., 19.11 feet, "S29 BT", Steel witness post with Survey marker sign, S.48 W., 2.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
 Surveyor's Michigan License No. 25849

Date 12 April, 1995