

Donald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-309

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	F9	SURVEY & REMONUMENTATION
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	MAY 10 1995
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

FILED
E 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
EC

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. James, in a field survey on November 29, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F9: PLS-Alfred Millard, DS, 1852, Set Or. Section Post- Spruce 10", N.57 W., 40 links, Y. Birch 10", S.50 E., 30 links. CCI Forestry Division, Land Corner Record Page 109, J.R. Radcliffe, RLS, 1965, Corner is iron pipe w/ brass cap set November 15, 1910. New references: Hemlock 8", EAST, 36.9 links, Cedar 12", S.65 W., 9.8 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F9: Found 2' cast steel monument with 3 1/4" brass cap marked to identify corner position, dated Nov. 15, 1910. Established locations for GLO BT's and made search for remains of BT's, results inconclusive. From monument measured west 1.71 chains (GLO record) to stream. Area around stream flooded and measurement is only approx., but is acceptable. Found monument and new witness trees of the report of J.R. Radcliffe, 1965, in excellent condition. Found old blaze lines east and west. Established additional reference trees. Corner lies on eastern slope of lowland around small stream and in mixed timber. Existing monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F9: Stamped P.A. 345 in brass cap of cast steel monument. Renewed existing reference trees w/BT signs and paint. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Ex. Hemlock 20", S.87 E., 24.08 feet, "Dbl Blz", Ex. Cedar 18", S.67 W., 7.30 feet, "Dbl Blz", Maple 7", S.24 E., 27.51 feet, "1/4s BT", Hemlock 8", N.13 W., 8.86 feet, "1/4s BT", Steel witness post with Survey marker sign, N.55 E., 2.0 feet. All bearings are magnetic.

Signed by Robert L. James Date 12 April, 1995
Surveyor's Michigan License No. 25849