

Approved by Alger County  
 Land Survey Re-monumentation  
 Peer Group Under Act 345 of  
 P.A. of 1990 On 9/17 1994

McE DAVIS  
 ACTING Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

4-261

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>63</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED  
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN  
 REGISTER OF DEEDS  
 ALGER COUNTY, MICH.

Register of Deeds Stamp & File Number

I, Robert L. James, in a field survey on July 17, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G3: P.L.S., Alfred Millard, DS, 1852. Set section post. Sugar 24, N.52 W., 14 links. Cedar 8, S.40 E., 19 links. George L. Depew, County Surveyor, December 1917, set iron corner from Gov't field notes. M.D.S.H. & T. Records - 1 1/2" Iron pipe shown on 1968 plans for State Hwy M-28, references, 12' Maple, S40 W., 4.38 feet, 3' Maple, S.70 W, 14.65 feet, 8' Cherry, N.60 E., 20.75 feet. Gerald W. Carlson, RLS, October 1977. Found 1 1/2" Iron pipe. Established references, 13' Maple, S.30 W., 4.70 feet, 9' Maple, N.90 W., 17.46 feet, 5' Twin Maple, N.51 E., 20.20 feet, 12' Tamarack, S.81 E., 32.42 feet. Record in filing No. 115 Alger County Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G3: Found 1 1/2" G.I.P., identified by references on recorded report, and a 2" G.I.P., 4 feet long lying by 1 1/2" G.I.P. Brass cap has been torn from 2" G.I.P., rivet holes remain and remains of base plate are evident on the other end. Corner was perpetuated with a brass capped monument by George L. Depew, CS, December 1917, set from Gov't field notes. Corner position also indicated in M.D.S.H. & T. records. Recorded by Gerald W. Carlson, R.L.S. in 1977 and is as recovered presently. Reference BT's were found as set and relate to corner position as recorded. Corner position is well documented and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G3: Set 2 1/4" x 30" Alum. Mon. w/3  
 1/4" Alum. cap stamped to I.D. corner.  
 Renewed existing reference trees w/BT  
 signs, blazed, scribed and painted. Set  
 PK nails for measuring w/brass I.D.  
 washers in the following reference  
 trees. Ex. Hemlock 18", S.83 E., 32.34  
 feet, "BT". Ex. Twin 6" Maple, N.47 E.,  
 20.05 feet, "BT". Ex. Maple 20", S.40  
 W., 4.59 feet, "BT". Ex. Maple 10",  
 N.85 W., 17.45 feet. Survey Marker  
 Post, N.41 E., 0.80 feet.

Signed by Robert L. James Date 10 July, 1994

Surveyor's Michigan License No. 25849