

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 9/17 1994

Mike Davis
 Acting Chairman
 For corners in

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-260

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>65</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on July 27, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

65: P.L.S., Alfred Millard, OS, 1852. Set post corner of Sections 9, 10, 15 & 16. Hemlock 8, S.40 W., 26 links. Y. Birch 10, N.45 E., 38 links. George Depew, County Surveyor, set iron corner 1916, from Government notes, no accesories given. Gerald W. Carlson, R.L.S., August 1977. Found 1 1/2" pipe w/brass cap 47 feet NE of centerline Soo Line Railroad. Established references, 6" Cedar, N.53 E., 25.72 feet, 4" Balsam, S.80 W., 12.69 feet, 8" Spruce, S.38 E., 38.82 feet, 9" Cedar, N.10 W., 32.78 feet. Recorded in filing No.108 Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

65: Found 2 1/4" G.I.P. w/brass cap, identified by references on recorded report, stamped March 1916, 30" above ground level and solid. Corner set by George L. Depew, CS, in 1916. Corner recovered by Gerald W. Carlson, R.L.S., 47 feet NE of Soo Line Railroad, in 1977. Corner reference BT's were found as set and relate to corner position as recorded. Corner position sets well with record information and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

65: Ex. 2 1/4" G.I.P. w/brass cap, stamped P.A. 345 in cap. Renewed existing reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Spruce 14", S.39 E., 38.76 feet, "BT". Ex. Balsam 6", S.79 W., 12.66 feet, "BT". Ex. Cedar 11", N.13 W., 32.76 feet, "BT". Ex. Cedar 7", N.52 E., 25.73 feet, "BT". Survey Marker Post, N.52 E., 0.90 feet.

Signed by Robert L. Jamros Date 10 July, 1994
 Surveyor's Michigan License No. 25849