

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 11/15 1994

Robert L. Jamros
 ACTING Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

4-258

For corners in

Alger (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>22W</u>	<u>H3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
 REGISTER OF DEEDS, Stamp & File Number
 ALGER COUNTY, MICH.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3								●					
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on June 26, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H3: P.L.S., Alfred Millard, DS, 1852. Set Qr. Sec. post. Spruce 12, N.52 E., 35 links. Hemlock 10, S.27 W., 48 links. Gerald W. Carlson, R.L.S., October 1977. Set 5/8" x 18" Iron w/RLS cap in centerline of N-S road, Equidistant on line. Established references, 10" Balsam, N.58 E., 53.29 feet, 15" Cedar, S.87 E., 44.68 feet, 7" Yellow Birch, S.50 W., 41.86 feet, 5" Balsam, S.70 W., 26.61 feet. Record in filing No. 115 Alger County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H3: Found 5/8" Rebar w/R.L.S. cap, identified by references on recorded report, in centerline of Deerton Road approx. 600 feet South of State Hwy. M-28. Rebar set by Gerald W. Carlson, R.L.S. equidistant (2658.65 ft.) on north line of Section 10 that measured in total 5317.30 ft. Recorded in filing No. 115, Alger County Records. A search was made at the original BT locations for remaining evidence of Hemlock and Spruce. Road and powerline construction has destroyed remaining evidence. Corner position sets well in the centerline of the Deerton Road and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H3: Set 5/8" x 18" Rebar w/3 1/4" Alum. cap stamped to I.D. corner Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Ex. Balsam 10", S.77 W., 26.62 feet. Maple 10", N.73 E., 50.28 feet, '1/4S-BT'. Maple 10", S.48 E., 67.66 feet, '1/4S-BT'. Maple 8", S.53 W., 51.75 feet, '1/4S-BT'.

Signed by Robert L. Jamros Date 10 July, 1994
 Surveyor's Michigan License No. 25849