

Approved by Alger County
 Land Survey Remonumentation
 Peer Group Under Act 345 of
 P.A. of 1990 On 9/17 1994

Mez Drulis
 ACTING Chairman
 For cornerers in

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-271

FILED
 TIME 2:35 p.m.

NOV 17 1994

DONALD W. KINNUNEN
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | | |
|---------------------------------------|---------------------------|---------------|
| Alger (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>47N</u> R <u>22W</u> | <u>H4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | ● | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Robert L. Jamros, in a field survey on July 10, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H4: Methods to be applied in establishing this corner position were part of instructions to Deputy Surveyors during the Public Land Surveys. Monuments were not installed at that time. Geo.L. Depew, CS, 1918. Center post established on true line East-West and North-South. Alger County Road Comm., H.H. Anderson, CE, 1935. Found iron at road station 42+53.2 as part of road alignment and construction of Deerton Road. Alger County Road Comm., E. Swan, RLS, 1946. Found 1" steel pin at road station 35+65.9 (Labled Center Post) as part of road alignment and construction of Deerton Road. Gerald W. Carlson, RLS, 1977. Set 5/8" x 18" iron w/RLS cap at distances compiled from road stations and alignment information as given on 1935 and 1946 Alger County Road Comm. plans. Established references, 6" Balsam, S.79 W., 66.54 ft., 12" White Birch, N.50 W., 49.60 ft., 10" White Birch, N.24 W., 91.82 ft. Recording No's. 115 and 278, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H4: Found 5/8" Rebar w/R.L.S. cap, identified by references on record report, 3 feet west of the centerline of Deerton Road and on centerline of gravel road to the west. Rebar set by Gerald W. Carlson, R.L.S. with reference to maps from Alger County Road Commission files. Recorded in filing No. 278 & 115 Alger County Records. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H4: Installed 3 1/4" Alum. cap on existing 5/8" Rebar, stamped to I.D. Corner. Est. reference trees w/BT signs, blazed, scribed and painted. Set PK nails for measuring w/brass I.D. washers in the following reference trees. Power Pole No. B68, N.83 E., 35.39 feet, "BT". W. Pine 7", S.51 W., 43.32 feet, "C1/4-BT". Ex. W. Birch 14", N.52 W., 50.0 feet, "BT". Maple 4", N.29 W., 75.65 feet, "C1/4-BT".

Signed by Robert L. Jamros Date 10 July, 1994

Surveyor's Michigan License No. 25849