

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-12-1995

JAN 23 1996

COMMISSION

4-352

Herald Carlson
Chairman
For corners in
Alger
(County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Corner Code #

- 1. Public Land Survey T 47N R 22W K13
T 46N R 22W K1
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

REC'D and FILED

JAN 23 1996
2:45 p.m.
DEPT. OF LAND & WATER, County Clerk

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on July 05, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K13: PLS-William A. Burt, DS, 1841, Set post corner of sections 35 & 36 - Maple 14', N.50 E., 3 links, Hemlock 6', N.10 W., 12 links. Alfred Millard, DS, 1852, recovered corner position during the GLO subdivision of T.46N., R.22W., added the following references. Hemlock 18", S.38 W., 50 links, Sugar 8", S.68 E., 35 links. William F. Bowman, RLS, 1990, Recovered a brass cap iron and remains of the GLO witnesses. Established new references. Hemlock 14', N.85 E., 12.5', Beech 7', S.05 E., 16.7', Beech 14", N.68 W., 9.9', Maple 14", S.46 W., 20.5', Sign Post, S.00W., 2.5'. Recorded in filing No. 4-131, Alger County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K13: Found 2' cast iron bar with 3 1/4" brass cap stamped to identify corner position dated Nov. 9, 1910. A search was made at GLO bearing tree locations, inconclusive. Found all reference trees and four inch post with sign as recorded in LCRC Report by William F. Bowman, LS, 1990. Corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K13: Stamped P.A. 345 in brass cap of cast steel monument. Renewed existing reference trees w/ BT signs and paint. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Hemlock 14", N.87 E., 12.50 feet, " S36 BT ", Ex. Beech 7", S.05 E., 16.66 feet, " S1 BT ", Ex. Beech 14", N.68 W., 9.83 feet, " S35 BT ", Ex. Maple 14", S.46 W., 20.45 feet, " S2 BT ", 4" Post w/ sign, South, 2.5 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

