

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. R. 22, 23 W.	A-8, A-9
2. PROPERTY CONTROLLING IN SECTION	19 T. 47 N. R. 22, 23 W.	10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 10-8 1973 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Woodpost:

Hemlock	22	N20°E	11 links
Maple	14	N64°W	40 links

A-9 Woodpost:

Tamarack	12	N62°E	50 links
Tamarack	10	N80°W	57 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-8 This corner was set mid-point & on a line between section corners north & south. Corner lies on east edge of old winter logging road.

A-9 This corner was set mid-point and on a line between section corner 1 mile north and section corner 1 mile south.

10 This corner was set mid-point and on a line between $\frac{1}{2}$ corner north and section corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: 1" pipe, 4" aluminum cap All bearings are magnetic

A-8 9" Hemlock ($\frac{1}{8}$) (NBT) N32°W 29.3'
12" R. Maple ($\frac{1}{8}$) (NBT) S64°W 38.2'

A-9 4" Cedar (S19) (NBT) N16°E 28.4'
9" Cedar (S24) (NBT) N57°W 17.5'

10 5" R. Maple (S 1/16) (BT) N23°E 10.6'
8" R. Maple (S 1/16) (BT) S 2°E 6.9'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray DATE 10-22-73
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575


**CORNER NUMBERING CODE DIAGRAMS FOR IDENTIFYING LAND CORNER
RECORDATIONS AND INDEXING**

FOR PUBLIC LAND SURVEY CORNERS IN THE
T. 27ⁿ, R. 22, 23^w (MENTIONED OVER)



Apply letter prefix for corner points encircled above for identifying corner recordation numbers over.

FOR PROPERTY CONTROLLING AND MISC.
PROPERTY CORNERS WITHIN THE SECTION
(MENTIONED OVER AND EXCLUDE LOT CORNER)



1. Above coded numbers are positioned on 1/16 fractional lines of the section.
2. Township corner code numbers shall be applied to corners of above typical section not numbered.
3. Miscellaneous property corners within a section, located at points other than numbered above, shall be referenced to at least two of above corner code numbers.
4. Private claim corners to be tied to rectangular land corners if possible -- sketch required below.

EXPLANATORY SKETCH IF NECESSARY -- BELOW

