

DEC 27 1999

Approved by Alger County Land Survey Remuneration Peer Group Under Act 248 of P.A. of 1990 On 12-8-1999

Guild W. Carlson Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Alger

(County)

Located In:

Corner Code #

05-152

1. Public Land Survey	T	48N	R	15W	A9
	T	48N	R	16W	M9
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

FILED TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on September 07, 1999, 19, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A9: PLS * William A. Burt, DS, 1841. * Set post corner of Sections 24 and 25 (T48N-R16W). * Beech 8", N.79 E., 52 links. * W.Pine 12", N.15 W., 11 links. * No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A9: Located corner search area by calculated position and standard field survey. Found Maple 24", dead and down, scribed "NBT, S25" at S.54 W., 6.3 feet, more or less, author unknown. Also found squared 6" Cedar post down and badly burned. Timber cruisers paint lines in all cardinal directions from downed post. Located GLO BT, W.Pine in the N.15 W., position. A portion of the lower blaze with axe marks and the scribing still visible. Set corner monument at S.15 E., 11 links from W.Pine stump. Corner position as established is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A9: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap. * Established the following reference trees with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D washers for measure in the following: Iwin Maple 10"-14", N.10 W., 5.37 feet, blazed only. * Maple 12", S.34 W., 28.22 feet. "S25 BT". * Maple 8", S.12 E., 10.38 feet, "S30 BT". * Maple 7", N.77 E., 22.11 feet, "S19 BT". * Survey marker sign on 6 foot steel post, S.26 W., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 13, 1999

