

SURVEY & REMONUMENTATION

JUL 30 1996

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1930 On 5/8 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

4-375

For corners in Alger Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T <u>48N</u>	R <u>15W</u>	89 _____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on February 15, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

B9: PLS-George E. Adair, DS, 1851, Set Cr. section post - Beech 10", N.27 1/2 W., 10 links, Maple 8", S.42 1/2 E., 18 links.***** Ray J. Brotherton, RLS, 1950, Set iron R/R rail from government beech bearing tree in Northwest location. As noted in leather bound books of GLO field notes, Page 91, T.48N., R.15W., Alger County Records. No references given. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B9: Found small gauge vertical railroad rail and three inch squared top picket at corner position. At GLO BT location found 22" dead beech stub eight feet high, N.27 1/2 W., 6.6 feet (10 links), with blazes and inside rotted away. Found two existing bearing trees standing and healthy, Believed to be set by Ray J. Brotherton. Renewed existing witnesses to current Alger County standards and established additional reference trees. Set monument at this position on north side of railroad rail. Rail was set from original bearing tree location and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B9: Installed Berntsen Mon. No. A1N830 along north side of railroad rail, Stamped to identify corner position. Established reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. Maple 12", S.22 E., 23.74 feet, " Obl. Blzd.", Ex. Maple 8", N.64 E., 9.32 feet, " Obl. Blzd.", Ex. Maple 9", N.29 W., 15.84 feet, " Obl. Blzd.", Maple 8", S.68 W., 26.51 feet, " 1/4s BT ", Survey marker sign on six foot steel post, S.67 E., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 June 1996

