

**SURVEY &  
REMONUMENTATION**

FEB 19 1998

05-54

Approved by Alcona County  
Land Survey Remonumentation  
Peer Group under Act 843 of  
P.A. of 1996 On 12-10-1997

Arvid W. Carlson  
Chairman

**LAND CORNER RECORDATION CERTIFICATE  
SECTION**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

Located In: \_\_\_\_\_

Corner Code # \_\_\_\_\_

FILED

TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>48</u>	R	<u>15</u>	<u>C1</u>	
	T	<u>49N</u>	R	<u>15W</u>	<u>C13</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. James, in a field survey on August 11, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C1: PLS - John Burt, OS, 1841 \* Set post corner of Sections 5 and 6 \* White Pine 16, N.40 E., 7 links \* White Pine 16, N.25 W., 26 links \*\*\*\* George E. Adair, OS, 1851 \* White Pine 28, S.45 E., 39 links \* White Pine 24, S.18 W., 29 links \*\*\*\* Dean C. DeLaMater, RLS, Michigan Department of Conservation, 1953 \* Established corner position from 4 original BT's still in place, 1 in fair condition, 3 in poor conditions \* Set 1 inch pipe w/ 4 inch brass cap \* Made the following witness's - White Pine stump 28, N.23 W., 65 links \* White Pine stump 36, S.10 E., 73 links \* Recorded in Liber 1, Page 39, Alger County records. \*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C1: Found 1 iron galv. iron pipe w/brass cap \* Located original BT positions and found 3 stumps of the 4 originals \* Recovered both BT's from the 1953 report - White Pine stump in the Southeast position in poor condition and White Pine stump in the Northwest position badly decayed \* Established 4 reference trees \* Monumented position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C1: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify corner position. Corner lies approx. 100 feet South of a East-West track road \* Established the following reference trees w/BT signs, blazed, scribed and painted. Set BX nails for measure w/Alum. I.D. washers in the following - Red Pine 8, S.75 W., 26.67 feet, '96 BT' \* Maple 5, N.56 W., 13.43 feet, '901 BT' \* Red Pine 8, N.13 E., 13.35 feet, '932 BT' \* Red Pine 7, S.07 E., 6.93 feet, '95 BT' \* Survey marker sign on 6 foot steel post, S.35 W., 1.0 feet \* All bearings are magnetic.

Signed by Robert L. James  
Surveyor's Michigan License No. 25849

Date 12/10/1997

