

DEC 27 1999

Approved by Alger County Land Survey Reauthorization Peer Group Under Act 345 of P.A. of 1990 On 12-8-99

Donald W. Carlson
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-159

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	C5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

FILED
 TIME 1:30 p.m.
 DEC 15 1999
 DONALD W. KINNUNEN
 REGISTER OF DEEDS
 ALGER COUNTY, MI
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on September 25, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C5: PLS * George E. Adair, DS, 1851. * Set post corner of Sections 7, 8, 17, and 18. * Beech 7", N.50 W., 33 links. * W.Pine 11", S.28 E., 30 links. **** C.C.I. Co., Forest Products Division. * Ray J. Brotherton, RLS, 1946. * Set iron spring leaf from pine stump BT. * Government pine BT stump is S.28 E., 30 links, notch and iron marks plain but in poor condition. * No references set. **** Michigan Department of Conservation, Forestry Division. * Dean C. DeLaMater, RLS, 1951. * One original BT in place, in poor condition. * Corner had been previously perpetuated by Ray J. Brotherton, RLS. * Set 1" iron pipe with 4" brass cap. * 12" W.Pine, N.64 W., 28 links. * 10" W.Pine, N.21 E., 28 links. * 12" W.Pine, S.24 E., 26 links. * Liber 2, Page 13, Alger County Corner Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C5: Located corner search area by calculated corner position and standard field survey methods. Found 1" iron pipe with 4" brass cap and iron spring leaf at corner position. Remains of GLO original BT, W.Pine 11", are badly decayed. Found reference trees of the 1951 report in good condition. Monuments as found at corner position are accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C5: Existing 1" iron pipe with 4" brass cap. * Renewed existing reference trees with BT signs and paint. * Established an additional reference tree with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: Existing - W.Pine 28", S.25 E., 17.73 feet. * Existing - W.Pine 22", N. 25 E., 18.98 feet. * W.Pine 20", N.54 W., 18.65 feet. * W.Pine 14", S.62 W., 8.96 feet, "S18 BT". * Survey marker sign on 6 foot steel post, N.38 W., 1.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Date Dec 15 1999
 Surveyor's Michigan License No. 25849

