

DEC 27 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12-8-1999

Donald W. Carlson Chairman

05-162

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION Alger (County)

- 1. Public Land Survey T 48N R 15W C10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

FILED TIME 1:30 p.m.

DEC 15 1999

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on August 16, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of row 10 and column C.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C10: PLS * George E. Adair, DS, 1851. * Set quarter section post. * Maple 12", N.24 E., 22 links. * Maple 12", S.65.5 W., 28 links. **** Michigan Department of Conservation, Forestry Division. * Billy D. Buckler, RLS, 1960. * This corner replaced wooden post found by Dean C. DeLaMater in 1951. * Found Maple stump in proper position. * Set 1" iron pipe with 4" brass cap. * 36" W.Pine stump, S.71 E., 51 links. * 24" W.Pine stump, N.11 E., 37.5 links. * Liber 2, Page 154, Alger County Corner Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C10: Located corner search area by calculated position and standard field survey methods. Found 1" iron pipe with 4" brass cap. Also found only 1 BT of the 1960 report, W.Pine stump 24", in good condition. Established additional reference trees. Corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C10: Existing 1" iron pipe with 4" brass cap. * Renewed existing BT with BT sign and paint. * Established new reference trees with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: Spruce 7", N.51 W., 5.45 feet, "1/4s BT". * W.Pine 6", S.13 W., 71.54 feet, "1/4s BT". * W.Cherry 5", S.51 E., 57.27 feet, "1/4s BT". * Survey marker sign on 6 foot steel post, N.62 E., 1.1 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Date Dec 15 1999 Surveyor's Michigan License No. 25849

