

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16/1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-113

For corners in

Form with fields for Alger (County), Located In, Corner Code #, and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

REGISTERED TIME 10:00 A.M. JAN 8 1999 DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot in cell E5.

I, Robert L. Jamros, in a field survey on October 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E1: P.L.S. - John Burt, DS, 1841. Set post corner of Sections 32 and 33. Fir 6, N.57°E., 27 links. Birch 16, N.65° W., 45 links. * George E. Adair, DS, 1851. W. Pine 14, S.41°E., 21 links, Y. Pine 10, S.30°W., 22 links. ***** Robert E. Schmeling, RLS, 1980. Reported the corner position was restored by R.J. Brotherton, RLS, in 1952 (unrecorded), from the W. Pine 14, S.41°E., 21 links and Y. Pine 10, S.30°W., 22 links. R.J. Brotherton installed a truck axle monument and 8" squared post and witnesses, * W. Pine stump 24", S.42 1/2°E., 65 links, * W. Pine stump 26", N.42°E., 86 links, * N. Pine 14", N.62 1/2°W., 1.96 chains, * N. Pine 17", S.66 1/2°W., 1.36 chains. * Robert E. Schmeling replaced truck axle with a 1" G.I.P. with brass cap. * New bearing trees, W. Pine stump 14", S.74°E., 10.3 feet, (NBT), N. Pine 8", due South, 67.1 feet, (S4 T48N NBT) and attached aluminum locator tag to existing 8" post. * Liber 1, Page 337, Alger County Corner Records. ***** No other corner of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E1: Located corner position by standard field survey and single proportionate measurement. Found monument of the 1980 report and accessories in good condition and in acceptable location. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E1: Existing 1" G.I.P. with brass cap. Renewed existing references with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following, Existing - White Pine stump 14", S.79°E., 10.98 feet, * Existing - Norway Pine 10", S.04°W., 66.92 feet, * Existing - Red Pine 20", N.56°W., 129.41 feet, * Existing - Red Pine 24", S.73°W., 90.12 feet, * Existing - White Pine stump 24", S.37°E., 56.3 feet, * Existing - White Pine stump 26", N.48°E., 42.8 feet, * Survey marker sign on 6 foot steel post, S.41°E., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

