

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

Robert L. Jamros
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-114

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>R15W</u>	<u>E 3</u>
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

FIELD
TIME 10:00 Am.

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3				●								
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on October 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E3: P.L.S. - George E. Adair, DS, 1851. Set post corner of Sections 4, 5, 8 and 9. * Beech 11, N.74°W. 38 links, Y. Birch 16, S.84°E. 18 links. ***** Dean C. DeLamater, RLS, 1954. Reported this corner was previously located by R.J. Brotherton, RLS. 1 original B.T. still in place, in excellent condition. Dean C. DeLamater installed a 1" G.I.P. with 4" brass cap and made the following references, 12" Beech, N.15°W., 23 links and 15" Beech, S.45°E., 56 links. * Liber 2, Page 75, Alger County Corner Records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E3: Located corner position by standard field survey. Found monument and 1 reference tree in good condition. Renewed 1 existing BT and established 3 additional reference trees. No original GLO evidence remains. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E3: Existing 1" G.I.P. with brass cap. Renewed existing BT with BT signs and paint. Established 3 additional reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following. * Existing - Beech 20", N.13°W., 14.94 feet. * Maple 5", N.55°E., 28.67 feet, "S4 BT". * Maple 5", S.01°W., 31.56 feet, "S9 BT". * Maple 5", S.74°W., 2.65 feet, "S8 BT". * Survey marker sign on 6 foot steel post, S.16°W., 0.60 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

