

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 1/16/1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-115

Robert L. Jamros
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R15W</u>	<u>E 4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FIELD
TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8	●	9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on July 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E4: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. * Beech 6, N.51° W., 56 links. * Hemlock 24, S.26°E., 6 links. ***** Robert E. Schmeling, RLS, 1980. Reported the corner position was restored by R.J. Brotherton, RLS, 1948, (unrecorded) from a Hemlock BT stump and a standing Beech BT. R.J. Brotherton installed an axle shaft and made a new bearing tree, Beech 12", N.30°W., 27 1/2 links. * Robert E. Schmeling observed the original evidence and replace axle shaft with 1" G.I.P. with brass cap and established the following. * Beech 18", due North, 23.5 feet (1/4 S9 NBT) * Beech 12", N.20°E., 22.2 feet (1/4 S9 NBT) * Beech 20", S.59°E., 25.3 feet (1/4 S9 NBT) * Beech 10", S.18°W., 11.3 feet (1/4 S8 NBT) * 5" squared cedar post with aluminum locator tag. * Liber 1, Page 323, Alger County Corner Records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E4: Located corner position by standard field survey and single proportionate measurement. Found monument of the 1980 report and accessories in good condition and in acceptable location. Observed the following evidence of GLO, decayed stump in Northwest position and Hemlock roots and stump hole in Southeast position. Also R.J. Brotherton BT, Beech 16" stump, S.26°E., 27 1/2 links. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E4: Existing 1" G.I.P. with brass cap. * Renewed existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following. * Existing - Beech 22", N.04°E., 23.20 feet. * Existing - Beech 15", N.18°E., 22.00 feet. * Beech 24", S.57°E., 24.67 feet. * Existing - Beech 13", S.18°W., 11.25 feet. * Survey marker sign on 6 foot steel post, East, 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

