

# SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-10-1997

## SECTION

05-53

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

(County)

Located In: \_\_\_\_\_

Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>48</u>	R	<u>15</u>	E5
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

FILED  
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. James, in a field survey on September 10, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E5: PLS - George E. Adair, DS, 1851 \* Set post at corner of Sections 8, 9, 16 & 17 \* Birch 12, N.20 E., 28 links \* White Pine 24, S.22 W., 24 links \*\*\*\* Dean C. DeLaMater, RLS, Michigan Department of Conservation, 1951 \* Corner position found while making partial resurvey of township - 1 original BT in place, fair condition \* Set 1 inch galv. iron pipe w/brass cap at corner position \* Witness's - Pine stub 30, S.52 E., 145 links \* White Pine 10, S.70 W., 162 links \* Recorded in Liber 2, Page 9, Alger County records. \*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E5: Found 1 inch galv. iron pipe w/brass cap and 6 inch squared, scribed post down and decayed \* Recovered BT's of the 1951 recorded report \* Renewed exist. BT's and established additional reference trees \* Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E5: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify the corner position \* Renewed exist. reference objects w/BT signs and paint \* Established additional reference trees w/BT signs, blazed, scribed and painted \* Set PK nails w/Alum. I.D. washers for measure in the following - Exist. BT, Pine stub 30, S.39 E., 95.80 feet, scribing evident \* White Pine 22, S.70 W., 127.25 feet \* White Pine 7, N.26 E., 33.94 feet. '63 BT' \* White Pine 9, N.58 W., 66.60 feet, '59 BT' \* Survey marker sign on 6 foot steel post, N.55 W., 2.0 feet \* All bearings are magnetic.

Signed by Robert L. James  
Surveyor's Michigan License No. 25849

Date 12/10/1997

