

SURVEY & REMONUMENTATION

JUL 30 1995

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/8 1996

Gerald Wilson
Chairman

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

4-377

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

For corners in _____ Located In: _____ Corner Code # _____

_____ Alger _____ (County)

1. Public Land Survey	T	<u>48N</u>	R	<u>15W</u>	E9		
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Section	S		T		R		
	S		T		R		

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on October 27, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E9: PLS-George E. Adair, DS, 1851, Set post corner of sections 20-21-28-29, Maple 9", N.77 1/2 W., 23 links, W.Pine 14", S.36 E., 24 links.***** Department of Conservation, Forstry Division, Dean C. DeLamater, RLS, 1954, This corner was established by double proportionate measurement, by forestry division survey crew, while making a partial resurvey of this township. One probable original BT still in place, badly burned. Set 1" pipe with 4" brass cap and established the following references, Red Pine 18", S.67 W., 82 links, W.Pine Stump 32", N.13 E., 104 links. Filing No. 62, Alger County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E9: Found one inch galvanized iron pipe with four inch brass cap stamped to identify corner position and 4" squared post. Also found 1954 witnesses, S.67 W., 82 links, a partially dead 26' Red Pine, and at N.13 E., 104 links, a 32" White Pine stump scribed "NBT". Existing monument was set, as stated in report of 1954, by double proportionate measurement. Corner position has been verified against corners South and East. Monument as set is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E9: Stamped P.A. 345 in existing four inch brass capped Department of Conservation Monument. Renewed existing reference stump w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees and or stumps. Ex. W.Pine Stump 32", N.19 E., 68.64 feet, " Ex. scribing NBT ", W.Pine 8", S.21 E., 30.69 feet " S28 BT ", R.Pine 12", S.56 W., 39.37 feet, " S29 BT ", R.Pine 12", N.62 W., 40.45 feet, " S20 BT ", Survey marker sign on six foot steel post, N.56 E., 1.35 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12 June 1996

