

SURVEY & REMONUMENTATION

JUL 30 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/8 1996

Gerald W. Cook
Chairman

4-378

For corners in Alger Located In: _____ Corner Code # _____
(County)

- | | | | | | |
|---|---|------------|---|------------|-------|
| 1. Public Land Survey | T | <u>49N</u> | R | <u>15W</u> | E10 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous
Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on October 27, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E10: PLS-George E. Adair, DS, 1851, Set Qr. section post - Beech 8", N.44 1/2 W., 38 links, W.Pine 26", S.20 E., 24 links.**** Department of Conservation, Forestry Division, Dean C. DeLamater, RLS, 1954, This corner was found by forestry division survey crew, while making a partial resurvey of this township. One original BT still in place and in fair condition. Set 1" pipe with 4" brass cap and established the following reference trees, W.Pine 14", N.25 E., 44 links, W.Pine 14", S.30 W., 45 links. Filing No. 66, Alger County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E10: Found one inch galvanized iron pipe with four inch brass cap and two existing bearing trees as stated in the 1954 report, blazes grown over. Existing monument was set as stated in 1954 report, from one original bearing tree still in place, in fair condition, - remains of original BT not apparent. Existing BT's upgraded to current Alger County standards and established additional references. Corner position has been verified against corners North and South. Monument as set is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E10: Stamped P.A. 345 in existing four inch brass capped Department of Conservation Monument. Renewed existing reference trees w/ BT signs and paint. Established additional reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees. Ex. W.Pine 24", S.86 W., 30.13 feet, " Dbl. Blzd.", Ex. W.Pine 28", N.29 E., 29.84 feet, " Dbl. Blzd.", Hemlock 5", N.50 W., 34.23 feet, " 1/4S BT ", Balsam 7", S.24 E., 16.78 feet, " 1/4S BT ", Survey marker sign on six foot steel post, S.49 W., 1.45 feet. All bearings are magnetic.



Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/29/95