

REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16/98

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-116

For corners in

Form with fields for Alger (County), Located In: T48N R15W, T49N R15W, Corner Code # F1, F13, and numbered sections 1-5.

Register of Deeds Stamp & File Number box containing TIME 10:00 A.M., JAN 8 1999, DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Grid table with columns A-M and rows 1-13, with a dot in cell F6.

I, Robert L. Jamros, in a field survey on October 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F1: P.L.S. - John Burt, DS, 1841. Set quarter section post. Beech 20, N.40°E., 48 links. Beech 10, N.22° W., 19 links. **** C.C.I. Co. Land Corner Records. Ray J. Brotherton, RLS, 1952. 4" post set straight line between section corners. * No Gov't BT's found. * 7" Maple, N.40°E., 15 1/2 links (NBT). * 18" Y. Birch, S.55°W., 25 links (NBT). **** Robert E. Schmeling, RLS, 1980. Recovered point of 4" post, Maple 7", N.40°E., 15 1/2 links (now 9") and Y. Birch 18", S.55°W., 25 links (now stump). * Replaced post point with 1" G.I.P. with brass cap. * Made new BT's. * Beech 17", N.09°E., 17.9 feet (1/4 S33 NBT). * Red Maple 12", S.14°E., 13.7 feet (1/4 S4 NBT). * Beech 12", S.48°W., 29.4 feet (1/4 S4 NBT). * Beech 8", N.66°W., 27.8 feet (1/4 S33 NBT). * Placed aluminum locator tag on 4" Red Maple 1.5 feet North. * Liber 1, Page 338, Alger County Corner Records. **** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F1: Located corner position by standard field survey and single proportionate measurement. Found monument of the 1980 report and accessories in good condition and in acceptable location. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F1: Existing 1" G.I.P. with brass cap. Renewed existing references with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following. * Existing - Beech 22", N.04°E., 18.26 feet. * Existing - Red Maple 18", S.16°E., 13.93 feet. * Existing - Beech 20", S.47°W., 29.52 feet. * Existing - Beech 10", N.67°W., 27.88 feet. * Existing - twin 5" Red Maple, North, 1.8 feet with aluminum locator tag. * Survey marker sign on 6 foot steel post, S.38°W., 0.8 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

