

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

05-117

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16 1998

McAmis RLS  
Chairman

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R15W</u>	<u>F 3</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>		
5. Private Claims <u>    </u>		

FIELD  
TIME 10:00 AM.

JAN 8 1999  
DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3					●							
4	7	8		9		10		11		12		
5												
6	18	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:

F3: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. Hemlock 9, N.52 1/2° W. 42 links. Hemlock 8, S.36°E., 10 links. \*\*\*\*\* Billy D. Buckler, RLS, 1960. This corner was reestablished midway and on line between section corners. No evidence of original corner. Placed 1" G.I.P. with brass cap. \* Witnesses, 12" Red Pine (1/4S NBT), S.02°E., 170 links. 13" W. Pine (NBT), S.56°E., 75 1/2 links. \* Liber 2, Page 165, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F3: Located corner position by standard field survey and single proportionate measurement. Found described monument of 1960 report in good condition and in acceptable location. Accessories, 12" Red Pine and 13" White Pine, are now stumps. Established new reference trees. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F3: Existing 1" G.I.P. with brass cap. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following. \* White Pine 12", N.55°W., 26.15 feet, "BT". \* White Pine 18", S.62°W., 22.28 feet, "BT". \* White Pine 5", S.53°E., 25.14 feet, "BT". \* White Pine 5", N.86°E., 64.02 feet, "BT". \* Survey marker sign on 6 foot steel post, S.52°E., 0.80 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

