

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

Robert L. Jamros
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-118

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T48N R15W	F 5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FIELD
TIME 10:00 Am.

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on September 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F5: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. Beech 12, N.04°E., 16 links. Beech 11, S.29°W., 12 links. ***** Dean C. DeLamater, RLS, 1951. This corner was established, by proportionate measurement. Set 1" G.I.P. with brass cap. Witnesses, 20" W. Pine, N.74°E., 219 links. 24" R. Pine, S. 30°E., 391 links. * Liber 2, Page 1, Alger County Corner records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F5: Located corner position by standard field survey and single proportionate measurement. Found monument and accessories of 1951 report in good condition and in acceptable location. Established new reference trees. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F5: Existing 1" G.I.P. with brass cap. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure in the following. * Maple 8", S.60°E., 43.97 feet, "1/4S BT". * Maple 12", S.34°W., 38.03 feet, "1/4S BT". * White Pine 8", N.84°W., 42.59 feet, "1/4S BT". * Maple 10", N.26°E., 84.59 feet, "1/4S BT". * Survey marker sign on 6 foot steel post, N.59°E., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1994

