

REF

DEC 27 1999

Approved by Alger County
Land Survey Re-enumeration
Peer Group Under Act 345 of
P.A. of 1990 On 12-8-1999

Donald W. Kinnunen
Chairman

For corners in SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-169

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	F7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
TIME 1:30 pm

DEC 17 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on June 08, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F7: PLS * George E. Adair, DS, 1851. * Set quarter section post. * Maple 6", N.28 W., 33 links. * Beech 6", S.30 E., 09 links. **** Michigan Department of Conservation, Forestry Division. * Billy D. Buckler, RLS, 1960. * This corner was reestablished midway and on line between 2 section corners. * No evidence of original corner. * Set 1" iron pipe with 4" brass cap. * 17" R.Pine, (1/4s NBT), N.18 W., 219 links. * 22" W.Pine stump (1/4s NBT), N.71 W., 65 links. * Liber 2, Page 155, Alger County Corner Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F7: Located corner search area by calculated position and standard field survey methods. Found 1" iron pipe with 4" brass cap. The references of the 1960 report, 17" R.Pine and 22" W.Pine stump have been removed and/or destroyed. Corner position as found lies 5.6 feet south of line and 5.3 feet west of midpoint between corners 1/2 mile east and 1/2 mile west. Established new reference trees to corner monument. Existing corner monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F7: Existing 1" iron pipe with 4" brass cap. * Established new reference trees with Bt signs, blazed, scribed and painted. * Set PK nails with aluminum I.D. washers for measure in the following: R.Pine 15", N.70 E., 30.58 feet, "1/4s BT". * W.Pine 16", S.34 E., 49.33 feet, "1/4s BT". * W.Pine 4", S.17 W., 27.67 feet, "1/4s BT". * R.Pine 7", N.50 W., 29.31 feet, "1/4s BT". * Survey marker sign on 6 foot steel post, S.80 E., 1.2 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 13 1999

