

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16 1998

McL Davis RLS  
Chairman  
For corners in

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

05-119

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R15W	<u>G1</u> ✓
	T49N R15W	G13
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1						●						
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. Jamros, in a field survey on October 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G1: P.L.S. - John Burt, DS, 1841. Set post corner of Sections 33 and 34. Hemlock 9, N. 71°E., 31 links. W. Pine 15, N.32°W., 43 links. \* George E. Adair, DS, 1851, Beech 8, S.41°E., 28 links. Beech 8, N.46°W., 10 links. \*\*\*\*\* Robert E. Schmeling, RLS, 1980. Reported that John R. Radcliffe, RLS, 1951, (unrecorded) recovered this corner from, W. Pine BT (stump), downed Hemlock tree and Beech, S. 41°E., was standing, and set 3" hardwood stake. Robert E. Schmeling recovered stake point and observed the original evidence. Replaced stake point with 1" G.I.P. with brass cap. Witnesses, Red Maple 8", S.44°W., 26.5 feet (S4 R15W NBT). Beech 21", due West, 26.9 feet (S33 T49N NBT). Red Maple 8", N.58°W., 15.8 feet (S33 R15W NBT). Red Maple 8", N.28°W., 20.7 feet (S33 T49N NBT). 6" squared cedar post with aluminum locator tag. Liber 1, Page 322, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G1: Located corner position by standard field survey and single proportionate measurement. Found monument and accessories of the 1980 report in good condition and in an acceptable location. Observed at N.32°W., 43 links a White Pine stump with scribing, "BT", and notch showing clearly. Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G1: Existing 1" G.I.P. with brass cap. Renewed existing reference trees with BT signs and paint. Set PK nails for measure with aluminum I.D. washers in the following. \* Red Maple 10", S.41°W., 26.27 feet. \* Beech 26", S.86°W., 26.77 feet. \* Red Maple 10", N.61°W., 15.46 feet. \* Red Maple 10", N.29°W., 20.72 feet. \* Survey marker sign on 6 foot steel post, S.36°W., 1.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

