

# SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 245 of  
P.A. of 1990 On 12-10-1997

05-52

Donald W. Kinnunen  
Chairman

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ (County)	Located In:	Corner Code #	
	48      15	G 2	
1. Public Land Survey	T <u>48</u> R <u>15</u>	<u>92</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

FILED  
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on August 11, 1997, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G2: PLS - George E. Adair, OS, 1951 \* Set quarter post \* Beech 8, N.30 W., 07 links \* Beech 5, S.59 1/2 E., 41 links \*\*\*\* J.R. Radcliffe, RLS, C.C.I. Co., Forestry Division, 1951 \* Set post at corner position from Government Beech BT's, No witness's \* Unrecorded \*\*\*\* Ray J. Brotherton, RLS, C.C.I. Co., Forestry Division, 1952 \* Recovered and replaced post set by J.R. Radcliffe with a new 6 inch fir post \* Established reference trees \* Crotched Maple 16, N.29 E., 6 links, scribed NBT \* Beech 12, S. 4 links, scribed NBT \* Unrecorded. \*\*\*\* Dean C. DeLaMater, RLS, Michigan Department of Conservation, 1953 \* 1 original BT still in place, in fair condition \* Replaced exist. post with 1 inch galv. iron pipe w/4 inch brass cap \* References to corner - Sugar Maple 20, N.28 E., 6 links \* Beech 12, S.05 E., 3 links \* Recorded in Liber 2, Page 72, Alger County records. \*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G2: Found 1 inch galv. iron pipe w/brass cap. \* Recovered 2 exist. BT's from 1952 Unrecorded report and 1953 recorded report \* Established new reference trees \* Monument position as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G2: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify corner position \* Renewed exist. reference tree w/BT signs and paint \* Established additional reference trees w/BT signs, blazed, scribed and painted \* Set PK nails for measure w/Alum. I.D. washers in the following - Beech 4, N.68 E., 27.00 feet, '1/4S BT' \* Exist. BT, Beech 14, S.11 W., 2.67 feet, no marks visible \* Maple 5, S.47 W., 19.24 feet, '1/4S BT' \* Maple 6, N.59 W., 10.23 feet, '1/4S BT' \* Survey marker sign on 6 foot steel post, S.72 W., 1.2 feet \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/10/1997

