

**SURVEY &
REMONUMENTATION**

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990, On 12/16 1998

Robert L. Jamros
Chairman
For corners in

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-120

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R15W</u>	<u>G 3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED

TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3							●						
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Robert L. Jamros, in a field survey on October 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G3: P.L.S. - George E. Adair, DS, 1851. Set post corner of Sections 3, 4, 9 and 10. Hemlock 11, N.50°W., 38 links. Hemlock 11, S.50°E., 9 links. ***** Dean C. DeLamater, RLS, 1954. Corner established by double proportionate measurement. No original evidence found. Set 1" G.I.P. with brass cap. Witnesses, 14" Spruce, S.18°W., 61 links. 24" W. Pine, N.65°W., 222 links. * Liber 2, Page 73, Alger County Corner Records. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G3: Located corner position by standard field survey and proportionate distances to adjacent corners. Found monument and accessories of 1954 report in good condition and in an acceptable location. Established additional reference trees. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G3: Existing 1" G.I.P. with brass cap. Renewed existing reference trees with BT signs and paint. * Established new reference trees with BT signs, blazed, scribed and paint. Set PK nails for measure with aluminum I.D. washers in the following * Existing - Spruce 24", S.23°W., 40.78 feet. * Existing - White Pine 36", N.66°W., 146.58 feet. * Spruce 4", S.68°E., 19.31 feet, "BT". * Spruce 4", N.18°E., 59.03 feet "BT". * Survey marker sign on 6 foot steel post, N.52°W., 0.70 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

