

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 12/16/1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-121

Chairman

For corners in

Form with fields for Alger (County), Located In: T48N R15W, Corner Code # G4, and numbered items 1-5.

Register of Deeds Stamp & File Number box containing TIME 10:00 A.M., JAN 8 1999, DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

I, Robert L. Jamros, in a field survey on October 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is present at the intersection of column G and row 4.

A. Description of original monument and accessories and/or subsequent restoration:

G4: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. Hemlock 14, N.70°E., 21 links. Maple 7, S.68°W., 9 links. \*\*\*\*\* Billy D. Buckler, RLS, 1960. Corner reestablished midway and on line between 2 section corners, no evidence of original corner. \* Set 1" G.I.P. with brass cap. \* Witnesses, 14" W. Pine stump, (1/4S NBT), N.70°W., 65 links. \* 36" W. Pine stump (1/4S NBT), N.35°E., 70 1/2 links. \* Liber 2, Page 163, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G4: Located corner position by standard field survey and single proportionate measurement. Found no monument or accessories at this location. Found monument and accessories of the 1960 report 74 feet South and 313 feet West of actual corner position. Destroyed monument and accessories. Monumented corner position midway and on line between section corners. Established new reference trees. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G4: Set Berntsen aluminum monument with 3 1/4" aluminum cap no. AINB30, stamped to identify corner position. \* Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following, \* White Pine 7", N.17°W., 19.43 feet, "1/4S BT"; \* White Pine 6", N.47°E., 39.32 feet, "1/4S BT"; \* Maple 5", S.49°E., 5.41 feet "1/4S BT"; \* White Pine 8", S.56°W., 79.07 feet, "1/4S BT". \* Survey marker sign on 6 foot steel post, S.43°W., 1.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

