

DEC 27 1999

Approved by Alger County  
Land Survey Re-monumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12-8-99

Heald W. Kinnunen  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

05-170

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	G6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

FILED  
TIME 1:30 pm

DEC 15 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Jamros, in a field survey on April 14, 1999, 19\_\_\_\_\_, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, \_\_\_\_\_ recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G6: PLS \* George E. Adair, DS, 1851. \* Set quarter section post. \* Hemlock 12", N.49 E., 46 links. \* Hemlock 9", S.60.5 W., 22 links. \*\*\*\* Michigan Department of Conservation, Forestry Division. \* Dean C. DeLaMater, RLS, 1951. \* This corner was established by proportionate measurement while making a partial resurvey of this township. \* Set 1" iron pipe with 4" brass cap. \* 26" W.Pine stump, S.55 E., 118 links. \* 12" H.Maple, S.48 W., 245 links. \* Liber 2, Page 5, Alger County Corner Records. \*\*\*\* No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
G6: Located corner search area by calculated position and standard field survey methods. Found 1" iron pipe with 4" brass cap. Also found both BT's of the 1951 report in good condition. Corner position as found lies 2.3 feet east of line and 0.9 feet south of proportional position between section corners 1/2 mile north and 1/2 mile south. Renewed existing references and established additional references. Existing corner monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G6: Existing 1" iron pipe with 4" brass cap. \* Renewed existing references with BT signs and paint. \* Established new reference trees with BT signs, blazed, scribed and painted. \* Set PK nails with aluminum I.D. washers for measure in the following: Existing - 26" W.Pine stump, S.48.5 E., 77.72 feet. \* Existing - 24" H.Maple, S.52.5 W., 161.72 feet. \* W.Pine 12", N.51 E., 228.95 feet, "1/4s BT". \* 18" H.Maple, N.52 W., 281.82 feet, "1/4s BT". \* Survey marker sign on 6 foot steel post, S.29 W., 1.5 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date Dec 15 1999

