

**SURVEY &
REMONUMENTATION**

JUL 30 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

4-381

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 5/8 1996

Herald Wilson

Chairman

For corners in

Alger (County)

Located In:

Corner Code #

FILED
TIME 3:00 p.m.

JUN 27 1996

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

- | | | | | | |
|---|---|------------|---|------------|-----------|
| 1. Public Land Survey | T | <u>48N</u> | R | <u>15W</u> | <u>69</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous
Property in Section | S | | T | | R |
| | S | | T | | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on October 27, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G9: PLS-George E. Adair, DS, 1851, Set post corner of sections 21-22-27-28, W.Pine 30", N.40 1/2 E., 20 links, Hemlock 18", S.40 1/2 W., 40 links.**** Department of Conservation, Forestry Division, Dean C. DeLamater, RLS, 1954, This corner was found by forestry division survey crew, while making a partial resurvey of this township. Two original BT's still in place, one in fair condition, one in poor condition. Set 1' pipe with 4" brass cap and established the following references, W.Pine Stump 28", N.28 W., 52 links, W.Pine Stump 30", S.39 W., 45 links. Filing No. 63, Alger County Records. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G9: Found one inch galvanized iron pipe with four inch brass cap and five inch squared post, scribed. Also found was two existing BT's, White Pine stumps as stated in 1954 report. Existing monument was set, as stated in 1954 report, from two original BT's still in place, one in fair condition, one poor, - are now obliterated. Corner position has been verified against corners West and South. Monument as set is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G9: Stamped P.A. 345 in existing four inch brass capped Department of Conservation Monument. Established new reference trees w/ BT signs, blazed, scribed and painted. Set PK nails for measure w/ Alum. I.D. washers in the following reference trees, W.Pine 10", N.40 E., 14.78 feet, " S22 BT ", W.Pine 9", S.57 E., 65.73 feet, " S27 BT ", Maple 12", S.50 W., 73.23 feet, " S28 BT ", W.Pine 6", N.28 W., 34.81 feet, " S21 BT ", Survey marker sign on six foot steel post, N.69 E., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros

Date 12/12/95

Surveyor's Michigan License No. 25849

