

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 345 of P.A. of 1990 On 1/26/99

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-122

Chairman For corners in

Alger (County) Located In: Corner Code # 1. Public Land Survey T48N R15W T49N R15W T R T R S T R S T R S T R 4. Lot No. Recorded Plat 5. Private Claims

TIME 10:00 A.M. JAN 8 1999 DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 1.

I, Robert L. Jamros, in a field survey on November 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H1: P.L.S. - John Burt, DS, 1841. Set quarter section post. Beech 5, N.66°E., 25 links. Hemlock 14, N.36°W., 14 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H1: Located search area for corner position by standard field survey and single proportionate measurement. Found squared 6" Cedar post, West 10 feet from corner position (author unknown) and blaze lines North-South and East-West. A search was conducted for GLO evidence, it was determined as lost. Monumented corner position as established, midway on line between section corners 1/2 mile East and West. Established new reference trees. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H1: Set Berntsen aluminum monument no. AINB30 with 4" aluminum cap, stamped to identify corner position. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following * Beech 5", N.10°W., 31.12 feet "1/4S BT"; * Beech 5", N.36°E., 29.75 feet, "1/4S BT"; * Beech 6", N.61 1/2°E., 6.16 feet, "1/4S BT"; * Beech 5", S.33 1/2°W., 14.54 feet, "1/4S BT". * Survey marker sign on 6 foot steel post, N.60°W., 1.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

