

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 12/16 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

05-123

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R15W	H 3
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

TIME 10:00 A.M.  
JAN 8 1999  
DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Robert L. Jamros, in a field survey on September 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

H3: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. Beech 16, S.40°W., 7 links. Sugar 10, N.81°E., 37 links. \*\*\*\*\* Billy D. Buckler, RLS, 1960, Corner reestablished midway and on line between section corners. Set 1" G.I.P. with brass cap. Witnesses, 14" Beech (1/4S NBT), N.40°E., 45 links. 14" Beech (1/4S NBT), S.36°E., 25 links. \* Liber 2, Page 164, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H3: Located corner position by standard field survey and single proportionate measurement. Found monument and 1 NBT of the 1960 report. Monument is located at an acceptable corner position. Established new reference trees. Monument as found is accepted as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H3: Existing 1" G.I.P. with brass cap. \* Renewed existing reference tree with BT signs and paint. \* Established new reference trees with BT signs, blazed, scribed and painted. \* Set PK nails for measure with aluminum I.D. washers in the following, \* Existing - Beech 26", S.32°E., 16.68 feet; \* Maple 9", S.70°W., 19.00 feet, "1/4S BT"; \* Maple 8", N.66°W., 32.80 feet, "1/4S BT"; \* Beech 10", N.27°E., 13.83 feet, "1/4S BT". \* Survey marker sign on 6 foot steel post, N.45°E., 1.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

