

DEC 27 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12-2-1999

Donald W. Carlson
Chairman

05-172

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 15W	H7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

FILED
TIME 1:30 pm

DEC 15 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Jamros, in a field survey on June 14, 1999, 19_____, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, _____ recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H7: PLS * George E. Adair, DS, 1851. * Set quarter section post. * Maple 6", S.60 E., 14 links. * Beech 13", N.75 W., 44 links. **** Michigan Department of Conservation, Forestry Division. * Billy D. Buckler, RLS, 1960. * This corner was reestablished by proportionate measure between section corner to East and witness corner to West. * No evidence of original corner. * Set 1" iron pipe with 4" brass cap. * 30" W.Pine stub (1/4s NBT), S.61 W., 85 links. * 16" W.Pine (1/4s NBT), S.07 E., 140 links. * Liber 2, Page 153, Alger County Corner Records. **** No other subsequent restoration of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H7: Located corner search area by calculated position and standard field survey methods. Found corner monument lost. Found reference BT's of 1960 report in good condition. Set corner position from existing BT's and set new monument. Corner position as restored lies 3.1 feet north of line and 2.2 feet east of the proportional position between section corner 1/2 mile east and witness corner to the west. Renewed existing references and established additional reference trees. Corner position as established from existing references is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H7: Set 2 1/2"x30" Berntsen aluminum monument No. A1NB30 with 3 1/4" aluminum cap stamped to identify corner position. * Renewed existing references with BT signs and paint. * Established new references with BT signs, blazed, scribed and painted. * Set PK nails with aluminum I.O. washers for measure in the following: Existing - W.Pine 36", S.01 E., 89.74 feet. * Existing - W.Pine stub 30", S.68 W., 53.29 feet, "BT". * W.Pine 10", S.36 W., 32.64 feet, "1/4s BT". * W.Pine stump 40", N.21 W., 65.75 feet, "BT". * Survey marker sign on 6 foot steel post, S.64 W., 1.0 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date Dec 13, 1999

