

SURVEY & REMONUMENTATION

FEB 23 1999

Approved by Alger County Land Survey Remonumentation Peer Group Under Act 245 of P.A. of 1990 On 1/16/1999

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

05-125

Chairman

For corners in

Form with fields for County (Alger), Located In (T48N R15W, T49N R15W), Corner Code # (11), and numbered sections 1-5 for survey details.

TIME 10:00 Am.

JAN 8 1999

DONALD W. KINNUNEN REGISTER OF DEEDS ALGER COUNTY, MI

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13, used for recording corner locations.

I, Robert L. Jamros, in a field survey on November 11, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

11: P.L.S. - John Burt, DS, 1841. Cedar 6" corner of Sections 34 and 35. Spruce 10, N.46°E., 18 links. \* George E. Adair, DS, 1851. Spruce 9, S.48°E., 29 links. Cedar 9, S.21°W., 20 links. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11: Located search area for corner position by standard field survey and single proportionate measurement between BT corners 1 mile West and 1/2 mile East. Corner position lies in road bed of an old railroad grade crossing a swamp and beaver pond. Found old blaze line running North from corner position. A search was conducted for GLO evidence, it was determined as lost. Monumented proportioned corner position and established reference trees. Corner position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11: Set Berntsen aluminum monument no. AINB30 with 4" aluminum cap, stamped to identify corner position. Established new reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following, \* Cedar 6", N.13 1/2°W., 31.66 feet, \*S34 BT; \* Cedar 5", N.47 1/2°E., 21.45 feet, \*S35 BT; \* Cedar 6", S.32°W., 10.61 feet, \*S3 BT; \* Cedar 4", N.78 1/2°E., 14.56 feet, \*S35 BT. \* Survey marker sign on 6 foot steel post, N.45°E., 10.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros Surveyor's Michigan License No. 25849

Date December 16, 1998

