

**SURVEY &  
REMONUMENTATION**

FEB 23 1999

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 245 of  
P.A. of 1990 On 12/16 1998

Robert L. Jamros  
Chairman

**SECTION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

05-126

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T48N R15W</u>	<u>12</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>		
5. Private Claims <u>    </u>		

TIME 10:00 AM

JAN 8 1999

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3	●	2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I2: P.L.S. - George E. Adair, DS, 1851. Set quarter section post. Cedar 15, N.30°W., 55 links. Y. Birch 16, S.58°E., 35 links. \*\*\*\*\* C.C.I. Co. Land Corner Records, Ray J. Brotherton, RLS, 1949. Set corner position from Y. Birch, S. 58°E., 35 links. Remains only of Cedar BT in Northwest position. Set 1" iron pin and 3" Cedar post. Witnesses, 9" Cedar, S.78°W., 9 links. 4" Maple, N.89°E., 16 links. Unrecorded. \*\*\*\*\* Robert E. Schmeling, RLS, 1980. Observed original evidence reported by Mr. Brotherton. Replaced 1" iron pin with 1" G.I.P. with brass cap. Witnesses, W. Pine 14", N.27°E., 39.4 feet (1/4 S2 NBT). W. Pine 16", S.70°E., 38.7 feet (1/4 S2 NBT). W. Pine 12", S.54°E., 25.5 feet (1/4 S2 NBT). W. Cedar 9", N.66°W., 6.0 feet (1/4 S3 NBT). \* Liber 1, Page 365, Alger County Corner Records. \*\*\*\*\* No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I2: Located search area for corner position by standard field survey and single proportionate measurement. Found NBT's of the 1949 restoration. Found monument and 3 NBT's of the 1980 report in good condition. W. Pine 14, N.27°E., 39.4 feet, is dead and down. \* Renewed existing and established new reference tree. Corner monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I2: Existing 1" G.I.P. with brass cap. Renewed existing reference trees with BT signs and paint. Established 1 new reference tree with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following, \* Existing - White Pine 22", S.68°E., 38.9 feet; \* Existing - White Pine 16", S.54°E., 25.73 feet; \* Existing - White Cedar 10", N.66°W., 6.03 feet; \* Existing - Maple 7", S.84°E., 10.3 feet; \* Cedar 10", S.79°W., 6.1 feet; \* Spruce 4", N.40°E., 22.85 feet, "BT". \* Survey marker sign on 6 foot steel post, S.39°W., 1.0 feet. \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date December 16, 1998

