

# SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 645 of  
P.A. of 1990 On 12-10-1997

05-49

Donald W. Kinnunen  
Chairman

## SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ (County)	Located In:	Corner Code #	
	40 15	I4	
1. Public Land Survey	T <u>40</u> R <u>15</u>		
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

FILED  
TIME 8:30 A.M.  
  
DEC 17 1997  
  
DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI  
  
Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on September 10, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10	●	11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I4: PLS - George E Adair, 19. 1951 \* Set quarter section post \* White Pine 8, N.66 W., 11 links \* White Pine 10, S.61 E., 25 links \* R.J. Brotherton, RLS, 1949 \* Set 4 inch post from Government BT remains in current position \* Witness's - White Pine stump 30, S.20 E., 33.8 feet with boat spike in place \* White Pine stump 26, N.13 1/2 W., 44.2 feet \* Report unrecorded \*\*\*\* Billy D. Buckler, PLS, Michigan Department of Conservation, 1960 \* This corner was replaced as set by R.J. Brotherton, RLS, 1 original BT in place \* Set 1 inch galv. iron pipe w/4 inch brass cap \* Witness's - White Pine stump 16, N.75 E., 56 1/2 links \* White Pine stump 36, S.20 E., 51 1/2 links (this stump marked by R.J. Brotherton with boat spike) \* Recorded in Liber 2, Page 162, Alger County records \*\*\*\* Robert E. Schmeling, RLS, 1980 \* Monument of the 1960 recorded report is missing and in its place is a leaf of a truck spring \* Found 4 inch squared cedar post remains in place nearby \* Replaced leaf of spring with a 1 inch galv. iron pipe w/brass cap stamped to identify corner position \* No witness's made \* Recorded in Libee 1, Page 377, Alger County records \*\*\*\* No other subsequent restoration.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I4: Found 1 inch galv. iron pipe w/brass cap stamped RLS 6017, 1980, Robert E. Schmeling \* Found remains of White Pine stump BT's (boat spike missing) \* Established new references in place of badly deteriorated White Pine stumps \* Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I4: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify the corner position \* Established the following reference trees w/BT signs, lower blazes, scribed and painted \* Set PK nails w/Alum. 1.0 washers for measure in the following - 1/4 in Black Oak 6, S.72 W., 47.72 feet, 'BT' \* Black Oak 10, S.20 W., 128.75 feet, 'BT' \* Black Oak 10, S.45 E., 139.72 feet, 'BT' \* No other witness available \* Survey marker sign on 4 foot steel post, N.66 E., 2.0 feet \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/10/1997

