

SURVEY & REMONUMENTATION

FEB 19 1998

Approved by Alger County Land Survey Remonumentation Peer Group under Act 130 of P.A. of 1990 On 12-10-97

SECTION

05-48

Donald W. Carlson
Surveyor

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ (County)

Located In:

Corner Code #

1. Public Land Survey	T	48	IS	IS
	T	15W	R	15W
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	T	_____
	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Section	S	_____	T	_____
	S	_____	T	_____

FILED
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on September 16, 1997, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

15: PLS - George E. Adair, DS, 1851 * Set quarter section post * White Pine 9, N.66 W., 11 links * White Pine 13, S.61 E., 25 links * Dean C. DeLaMater, RLS, Michigan Department of Conservation, 1951 * Corner found while making partial resurvey of this township * Corner previously located and perpetuated by R.J. Brotherton, RLS * Replaced exist. monument w/1 inch galv. iron pipe w/4 inch brass cap * Witness's - White Pine stump 40, S.30 E., 97 links * White Pine stump 32, S.70 W., 94 links * Recorded in Liber 2, Page 4, Alger County records. **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

15: Found 1 inch galv. iron pipe w/brass cap and truck spring leaf * Corner position 1/2 mile North also had a truck spring leaf for a monument. * Recovered BT's of the 1951 recorded report * Measurements to adjacent corners check very well. * Renewed existing BT's and established additional reference trees * Monument position as found is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

15: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify the corner position * Renewed exist. BT's w/BT signs and paint * Established additional referene objects w/BT signs, scribed and painted * Set PK nails w/Alum. I.D. washers for measure in the following - Exist. BT, White Pine stump 40, S.20 E., 64.19 feet, scribing visible * Exist. BT White Pine stump 32, S.71 W., 61.87 feet, scribing visible * White Pine stump 26, S.56 W., 46.17 feet, "BT" * White Pine stump 50, N.56 E., 42.17 feet, "BT" * Survey marker sign on 6 foot steel post, N.05 W., 1.0 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

