

**SURVEY &  
REMONUMENTATION**

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 845 of  
P.A. of 1990 On 12-10-1997

Gerald W. Carlson  
Chairman

SECTION 05-47

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED  
TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

For corners in \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

		48 IS	<u>J1</u>
1. Public Land Survey	T	<u>48R</u> R <u>IS</u>	<u>J1</u>
	T	<u>49N</u> R <u>15W</u>	<u>J13</u>
	T	_____ R _____	_____
	T	_____ R _____	_____
2. Property Controlling in Section	S	_____ R _____	_____
	S	_____ R _____	_____
3. Miscellaneous	S	_____ R _____	_____
Property in Section	S	_____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, ROBERT L. JAMROS, in a field survey on September 17, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

J1: RLS - John Burt, CG, 1841 \* Set quarter section post \* Beech 10, N.71 E., 36 links \* Sugar 13, N.18 W., 19 links \*\*\*\*\* R.J. Brotherton, RLS, 1949 \* Set 4 inch post and iron pin from original Sugar 8T, N.18 W., 19 links, in a down position. \* Established witness's - Sugar 8, S.21 W., 12 links \* Sugar 6, S.41 1/2 E., 45 links \* Sugar 14, N.29 W., 35 links \* Unrecorded. \*\*\*\*\* T.J. McLaren, C.C.T. Co., Forestry Division, 1967 \* Post and iron pin set by R.J. Brotherton \* Sugar 8, S.21 W., 12 links \* Sugar 6, S.41 1/2 E., 45 links \* Sugar 14, N.29 W., 35 links \* Unrecorded \*\*\*\*\* Robert E. Schaeffling, RLS, 1980 \* Recovered R.J. Brotherton's monument and evidence at corner position and set a 1 inch by 4 inch galv. iron pipe w/brass cap \* Established new bearing trees - Hard Maple 8, S.38 W., 23.0 feet \* Hard Maple 20, N.74 W., 34.3 feet \* Hard Maple 14, N.61 E., 30.8 feet \* Hard Maple 9, due East, 21.0 feet \* Recorded in Liber 1, Page 359, Alger County records. \*\*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J1: Located corner position and found 1 inch galv. iron pipe w/ 3 1/2 inch brass cap and 3 exist. BT's from the 1949 unrecorded and 1980 recorded reports. All other BT's have been cut down or are down and dead \* Renewed exist. BT's and established additional reference trees. \* Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J1: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify corner position \* Renewed exist. BT's w/signs and paint \* Established 2 addition reference trees w/BT signs, blazed, scribed and painted \* Set PK nails for measure w/Alum. I.D. washers in the following - Exist. BT, Hard Maple 9, S.39 W., 24.69 feet, marks visible \* Exist. BT, Hard Maple 11, S.88 E., 21.02 feet, marks visible \* Maple 7, N.26 E., 17.61 feet, "1/4S BT" \* Maple 10, N.18 W., 24.26 feet, "1/4S BT" \* Survey marker sign on 6 foot steel post, S.80 W., 2.0 feet \* All bearings are magnetic.

Signed by Robert L. Jamros  
Surveyor's Michigan License No. 25849

Date 12/10/1997

