

**SURVEY &  
REMONUMENTATION**

FEB 19 1998

Approved by Alger County  
Land Survey Remonumentation  
Peer Group Under Act 315 of  
P.A. of 1980 On 12-10-1997

SECTION

05-416

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in \_\_\_\_\_

Located In:

Corner Code #

1. Public Land Survey	T <u>48</u> R <u>15</u>	<u>K1</u>
	T <u>49N</u> R <u>15W</u>	<u>K19</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

TIME 8:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN  
REGISTER OF DEEDS  
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. James, in a field survey on September 17, 1997, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K1: PLS - John Bart. OS, 1841 \* Set post corner of Sections 35 and 36 \* Beech 16, N.65 E., 17 links \* Beech 16, N.06 W., 15 links \*\*\*\* George E. Adair, OS, 1851 \* Beech 10, S.54 W., 35 links \* Beech 7, S.30 1/2 E., 27 links \*\*\*\* R.J. Brotherton, RLS, 1949 - Set post and iron pin from Birch line tree East of corner and 4 rounds at corner position at correct original locations \* Established witness's - Sugar 11, S.05 1/2 E., 44 links \* Sugar 16, S.84 1/2 W., 43 links \* Unrecorded \*\*\*\* T.J. McLaren, D.O.I. Co., Forestry Division, 1967 \* Post and iron set by R.J. Brotherton \* Sugar 11, S.05 E., 28.8 feet \* Sugar 16, S.85 W., 28.0 feet \* Unrecorded \*\*\*\* Robert E. Schmeling, RLS 1975 \* Recovered R.J. Brotherton's monument and evidence at corner position and set a 1 inch by 4 foot galv. iron pipe w/brass cap \* Established new bearing trees - Yellow Birch 19, S.40 E., 35.7 feet \* Hard Maple 15, S.30 W., 45.1 feet \* Beech 12, N.16 E., 24.1 feet \* Hard Maple 17, N.50 W., 69.4 feet \* Recorded in Libe 1, Page 81 of Alger County records. \*\*\*\* No other subsequent restoration on record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K1: Located corner position and found 1 inch galv. iron pipe w/3 1/2 inch brass cap and 1 exist. BT from the 1949 unrecorded and 1975 recorded reports \* All other BT's have been cut down or are dead stubs \* Renewed exist. BT's and established additional reference rees. \* Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K1: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify corner position \* Renewed exist. BT w/signs and paint \* Established 3 additional reference trees w/BT signs, blazed, scribed and painted \* Set PK nails for measure w/Alum. I.D. washers in the following \* Exist. BT, Hard Maple 16, S.31 W., 44.78 feet, marks visible \* Maple 6, N.65 E., 22.32 feet, "1926 BT" \* Beech 10, S.31 E., 39.28 feet, "1911 BT" \* Maple 12, N.55 W., 20.91 feet, "1935 BT" \* Survey marker sign on 6 foot steel post, S.49 W., 2.0 feet \* All bearings are magnetic.

Signed by Robert L. James

Date 12/10/1997

Surveyor's Michigan License No. 25849

