

Gerald Carlson
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

5-33

For corners in
ALGER
 (County)

Located In: _____ Corner Code # _____

| | | | | | |
|---|---|-----|---|-----|----|
| 1. Public Land Survey | T | 48N | R | 15W | K4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
 TIME 2:00 pm.
 MAR 31 1997
 DONALD W. KINNUNEN
 REGISTER OF DEEDS
 ALGER COUNTY, MI
 Register of Deeds Stamp & File Number

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 6 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Robert L. Jamros, in a field survey on October 22, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K4: PLS - George E. Adair, DS, 1851, Set quarter Section post * Y. Birch 8, N.31 W., 22 links * Beech 11, S.70 E., 23 links **** Ray J. Brotherton, RLS, 1949. * Set iron and post from original Y. Birch 8T, N.31 W., 22 links. * Witness, Sugar 3", N.50 W., 23 links. * Sugar 12", S.47 E., 38 links. * C.C.I.Co. Records. **** T.J. McClaren, C.C.I.Co., 1967. * Found post set by Ray J. Brotherton and two reference trees. * C.C.I. Records. **** Robert E. Schmeling, RLS, 1980. * Found decayed post on ground, recovered point. * Also found 1949 reference trees, Sugar 8", N.50 W., 23 links and Sugar 16", S.47 E., 38 links. * Set at recovered point location a 1" diam. 4 foot long galvanized iron pipe with brass cap stamped to identify corner position. * Witness, Hard Maple 14", N.35 E., 24.7 feet, scribed. * Hard Maple 11", S.34 E., 38.5 feet, scribed. * Beech 11", S.41 W., 34.5 feet, scribed. * Hemlock 8", N.20 W., 26.6 feet, scribed. * Recorded in L.1, P. 362, Alger County Records. * No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K4: Located existing 1" diam. galvanized iron pipe with brass cap and two existing BT's, 1949 unrecorded report. * Sugar 3", N.50 W., 23 links and Sugar 12", S.47 E., 38 links. * Also found four existing BT's from 1980 report, with one being a dead stub. Beech 11", S.41 W., 34.5 feet. * Remains of GL0 BT Y. Birch 8", (now stump) quite evident, N.31 W., 22 links. * Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K4: Stamped P.A. 345 in the existing brass capped monument. Renewed three existing reference trees w/ BT signs and paint. Established additional reference tree w/ BT signs, blazed, scribed and painted. Set Pk nails for measure w/ Alum. I.D. washers in the following reference trees. * Exist. BT, Hemlock 12", N.19 W., 26.31 feet, marks visible. * Exist. BT, Maple 20", N.35 E., 24.38 feet, marks visible. * Maple 20", S.33 E., 24.38 feet, marks visible. * Maple 7", S.17 W., 24.85 feet, '1/4S BT'. * Survey marker sign on six foot steel post, N.55 W., 1.5 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
 Surveyor's Michigan License No. 25489



Date 25 March, 1997