

**SURVEY &
REMONUMENTATION**

FEB 19 1998

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1993 Ch. 12-10-1997

SECTION

05-49

Gerald W. Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ (County)	Located in:	Corner Code #
	48 15	L3
1. Public Land Survey	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FILED
TIME 9:30 AM.

DEC 17 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert L. Jamros, in a field survey on September 14, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L3: PLS - George E. Adair, DS, 1851 * 1st quarter section post * Beech 8, N.14 W., 19 links * Beech 10, S.18 E., 14 links **** R.J. Brotherton, RLS, C.C.I. Co., Forestry Division, 1949 * Set 5 inch post from Government Beech BT's, in poor condition * Witness's - Sugar 14, S.35 1/2 W., 32 1/2 links * Sugar 14, South 22 1/2 E., 24 links * Unrecorded. **** T.J. McLaren, C.C.I. Co., Forestry Division, 1967 * Recovered exist. monument and witness's made by R.J. Brotherton in 1949 * Government Beech BT's, both in bad shape, quite rotten, but still standing and green. * Unrecorded. **** Robert E. Schmeling, RLS, 1980 * Recovered post point and BT's of R.J. Brotherton, 1949 * Government Beech BT's in poor condition * Replaced post point with 1 inch galv. iron pipe w/brass cap and placed squared 5 inch cedar post w/locator tag nearby * Witness's - Beech 11, N.74 W., 37.5 feet * Hard Maple 8, N.36 W., 45.0 feet * Hard Maple 11, N.26 E., 33.3 feet * Hard Maple 11, N.58 E., 53.7 feet * Recorded in Liber 1, Page 369, Alger County records. **** No other subsequent restoration on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L3: Found 1 inch galv. iron pipe w/brass cap and 5 inch squared cedar post w/locator tag * Renewed exist. and established new reference trees * Monument as found is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L3: Exist. 1 inch galv. iron pipe w/brass cap as stamped to identify the corner position * Renewed exist. reference trees w/BT signs and paint * Established additional reference trees w/BT signs, blazed, scribed and painted * Set PK nails w/Alum. I.D. washers for measure in the following - Exist. BT, Hard Maple 14, N.43 W., 45.10 feet * Exist. BT, Hard Maple 15, N.27 E., 33.58 feet * Exist. BT, Hard Maple 16, N.60 E., 53.44 feet * Beech 9, S.67 W., 18.12 feet, '1/4S BT' * Survey marker sign on 6 foot steel post, S.49 E., 2.0 feet * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date 12/10/1997

