

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43. NR. 15. W.

----- Alger ----- COUNTY

DESCRIPTION OF CORNER ~~Section Corner common to Sections 20, 21, 28, 29~~ -----

DESCRIPTION OF CORNER MONUMENT ~~1" Pipe with 4" Brass cap~~ -----

WITNESSES TO CORNER -----

~~18" Red Pine - S 67 E - 82 Links~~ -----

~~32" W. Pine Stump - N 13 E - 104 Links~~ -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. One probable original B.T. still in place, badly burned.

Corner was placed and witnessed October 21, 1953.

SURVEYORS SEAL

SIGNED *John C. DePelle* DATE *1/22/54*
REGISTERED LAND SURVEYOR