

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 NR. 15 W.
T. 49 NR. 15 W.

Alger

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 6 & 31

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER

36" N. Pine Stump - N 75 E - 50 Links

30" W. Pine Stump - S 65 W - 37 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew, while making a partial resurvey of this area. In the absence of any original evidence at the corner, it was placed in line, and at a proportionate distance between the two Section Corners.

Corner was placed and witnessed October 21, 1953.

SURVEYORS SEAL

SIGNED

Sam C. S. Suter
REGISTERED LAND SURVEYOR

DATE 1/22/56